BRUHAT BANGALORE MAHANAGARA PALIKE

3BMP/2014-15/OW/WORK_INDENT14544/CALL-:

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/09/2014-15, Date: 23.01.2015

Construction of Immersion Tank for Lord Ganesha idols at Near Rachenahalli Lake in Ward No 06 Byatarayanaprua Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M B HOMBAL	
				In Figures	In Words
1	864	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum	260.0	Rupees Two Hundred Sixty Only
2	27	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth,	Cum	4830.0	Rupees Four Thousand Eight Hundred Thirty Only
3	83.19	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2014-15	cum	3830.0	Rupees Three Thousand Eight Hundred Thirty Only
4	222.52	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2014-15	Cum	4535.0	Rupees Four Thousand Five Hundred Thirty Five Only
5	25.21	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum	Cum	6060.0	Rupees Six Thousand Sixty Only
6	191.97	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2014-15	Sqm	87.0	Rupees Eighty Seven Only
7	0.63	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46.2/ PWD SR 2014-15	Tone	77300.0	Rupees Seventy Seven Thousand Three Hundred Only

ಕಾ.ಇ. (ಪಾ.ವಿ)

8	10.5	Supplying and fixing M.S rectangular poles made out of 2 equal angles of 65x656 mm welded together and fixed in CC (1:2:4) with 2 NOS 16 mm dia, M.S hold fast rods each of length 25 cms, including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete), No. 252/ Item No. 37.2 PWD SR 2014-15	Mtr	1050.0	Rupees One Thousand Fifty Only
9	45	Providing and fixing M.S. Block pipe of 39 mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two vertical poles (M.S rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the engineer in charge of work etc, complete including two coats of approved quality paint over one coat of shop paint, No. 252/ Item No. 37.4 PWD SR 2014-15	Mtr	310.0	Rupees Three Hundred Ten Only
10	22.5	Providing chain link fencing 50 mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall bed welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the engineer – in charge of work including two coats of approved quality paint over one coat of shop paint, No. 252/ Item No. 37.3 PWD SR 2014-15	Sqm	650.0	Rupees Six Hundred Fifty Only
11	432	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	67.0	Rupees Sixty Seven Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92